BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No: EE/YNK/BBMP/E-PMT/20/2017-18 Dated: 23-02-2018

APPROVED TENDER SCHEDULE –'B'

Item No: 15

Name of Work:- Improvements to Dhobighat at Ananthpura in ward no 03, Attur

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri SANTHOSH B	
				Rate	Rate in Words
1	KKSRRB 300-1,Earth work excavation by manual means in ordinary soil involving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no19.1,Page no142, PWD SR 2016-17)	Cum	161.43	86.88	Rupees Eighty Six and Paise Eighty Eight Only
2	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/sand/ kanker/Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no130,PWD SR 2016-17)	Cum	161.43	99.16	Rupees Ninety Nine and Paise Sixteen Only
3	KSRRB M2100 PCC 1 KSRRB M2100-10. Plain cement concrete M10 with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @ 0.56cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days complete as per specifications MORTH Specification No. 2100 (P No. 218/27.18)	Cum	63.69	5969.05	Rupees Five Thousand Nine Hundred Sixty Nine and Paise Five Only
4	Providing laying palin / reinforced cement concrete for Side Drain using M20 normal mix concrete with OPC cement at 300kgs with 20 mm and down size granite metal coarse aggregates @0.69cum and fine aggregates @machine mixed, Well compacted for wall and bottom including centering shuttering Cost of material HOM of machinery curing etc excluding cost of steel as per MORTH Specification No. 1500,1700,2200 walls & bottomof thicknes 15(Page. 265 / Item.No. 37.59.2)	Cum	6.87	7350.60	Rupees Seven Thousand Three Hundred Fifty and Paise Sixty Only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri SANTHOSH B	
				Rate	Rate in Words
5	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per specifications.Specification noKBS 4.6.3,TMT bars Fe55 0(pwd sr2016-17,p.no17,s.no4.46)	Tonne,s	0.48	60073.05	Rupees Sixty Thousand Seventy Three and Paise Five Only
6	Providing and fixing Precast RCC Slabs as Per approved design, specification and Direction Engineer-in-Charge. (Approved Data Rate).	Sqm	18.90	2098.95	Rupees Two Thousand Ninety Eight and Paise Ninety Five Only
7	KSRB M2200-5.11.Design mix M20 with OPC cement @320 kgs,with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming to IS9103-1999 Reaffirmed-2008.etc as per specification&direction of the engineer incharge of work (pwd sr2016-17,p.no216,sno28.7.9)	Cum	40.36	7576.21	Rupees Seven Thousand Five Hundred Seventy Six and Paise Twenty One Only
8	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift.(P.No 174, I.No 22.7)	Sqm	403.63	95.35	Rupees Ninety Five and Paise Thirty Five Only
9	Providing groove cutting for width of 5mm to 10mm and depth 80mm- 100 mm including cost of cutting machine, generator & HOM of machinery, including cost of blade,coolant etc., including cleaning of groove & providing sand and hot bitumen fillars, and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications (P.No 175, I.No 22.8.1)	Rmt	114.00	121.84	Rupees One Hundred Twenty One and Paise Eighty Four Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.